

SOUTH CENTRAL RLY

**HYDERABAD
DIVISION-S AND T
2nd Floor, S and T
Department,
Hyderabad Bhavan,
Secunderabad.
Secunderabad,
500017
Telangana, India**

**Letter No: HYDERABAD DIVISION-S AND T /
Y-SG-36-2023-24-09 / 00850890090468**

Dated: 06/11/2023

**M/s ARECA EMBEDDED SYSTEMS PVT
LTD-HYDERABAD.**

Plot No.5B, Sy. No.184-185
Phase-V, IDA Cherlapally
Hyderabad.- 500051
Telangana, India

Sub: Letter Of Acceptance

- Ref:**
1. Tender No. Y-SG-36-2023-24-09 closing date 24-08-2023 11:30 for Hyderabad Division:- -Gati Shakti: Provision of Signal & Telecom Arrangements at ABSS stations (17 Nos) at Malakpet, Yakutpura, Huppuguda, Umdanagar, Shadnagar, Jedcherla, Mahabubnagar, Kurnool City, Sri Balabramareshwara Jogulamba & Gadwal on SC-DHNE section and Umri, Dharmabad, Basar, Nizamabad, Kamareddi, Medchal & Malkajgiri on SC-MUE section in connection with the works of "Soft Upgradation, Divyangjan facilities" under "AMRIT BHARAT STATION SCHEME" (ABSS).
 2. Your bid ID **15627600** dated **24/08/2023 09:51**
 3. Your Negotiation bid IDs [**15884340** dated **20/10/2023 11:20**]

The Competent Authority has accepted your offered rates in connection with the subject work. The total cost of the work at the accepted rates works out to Rs. 127330837.28 (Rupees Twelve Crore Seventy-Three Lakh Thirty Thousand Eight Hundred And Thirty-Seven Rupees And Twenty-Eight Paise Only)

A sum of Rs.731700 deposited as Earnest Money vide IREPS reference ID PE825819680347 has been retained towards initial Security Money for due and faithful fulfillment of the contract, and the balance Security Money will be recovered from the progressive

bills @ 6 % of the bill amount till it reaches 5 % of the contract value in terms of clause 16(1) of GCC.

You are requested to submit Performance Guarantee in the form as given in Clause 16 (4) of GCC equivalent to 5 % of the contract value amounting to Rs. 6366541.86 (Rupees Sixty-Three Lakh Sixty-Six Thousand Five Hundred And Fourty-One Rupees And Eighty-Six Paise Only) within 21 days from the date of issue of Letter of Acceptance, valid up to stipulated date of completion plus 60 days so that contract agreement can be executed.

The entire work shall be completed within 18 month from the date of issue of Letter of Acceptance.

Performance Guarantee (PG): The successful bidder shall have to submit a Performance Guarantee (PG) within 21 (Twenty one) days from the date of issue of Letter of Acceptance (LOA). Extension of time for submission of PG beyond 21 (Twenty one) days and upto 60 days from the date of issue of LOA may be given by the Authority who is competent to sign the contract agreement. However, a penal interest of 12% per annum shall be charged for the delay beyond 21(Twenty one) days, i.e. from 22nd day after the date of issue of LOA. Further, if the 60th day happens to be a declared holiday in the concerned office of the Railway, submission of PG can be accepted on the next working day.

a): In all other cases, if the Contractor fails to submit the requisite PG even after 60 days from the date of issue of LOA, the contract is liable to be terminated. In case contract is terminated railway shall be entitled to forfeit Earnest Money Deposit and other dues payable against that contract. In case a tenderer has not submitted Earnest Money Deposit on the strength of their registration as a Startup recognized by Department of Industrial Policy and Promotion (DIPP) under Ministry of Commerce and Industry, DIPP shall be informed to this effect. The failed Contractor shall be debarred from participating in re-tender for that work. The format for submission of Bank Guarantee is enclosed. This PG shall be initially valid up to the stipulated date of completion plus 60 days beyond that.

b): Performance Guarantee to be deposited in favor of SENIOR DIVISIONAL FINANCE MANAGER/ HYDERABAD DIVISION, SOUTH CENTRAL RAILWAY, SECUNDERABAD.

1) Section of work: SC-MUE & SC-DHNE Sections

2) Officer in charge: ADSTE/HYB, ADSTE/North/HYB & ADSTE/South/HYB

3) Telecom Supervisor in charge: SSE/Tele/KCG, SSE/Tele/MBNR, SSE/Tele/GWD, SSE/Tele/KRNT, SSE/Tele/MJF, SSE/Tele/MED & SSE/Tele/NZB.

- 4) Stores-receipts/issues: SSE/Tele/Stores/LGD
- 5) Materials inspected by Receipts/issues: Offi: ADSTE/HYB
- 6) Materials inspected by Receipts/issues: Supe: SSE/Tele/Stores/LGD
- 7) Recording of measurements for Supply Portion: ADSTE/HYB
- 8) Recording of measurements for Supply Portion: SSE/Tele/Stores/LGD
- 9) Recording of measurements for Labour Portion: ADSTE/HYB, ADSTE/North/HYB & ADSTE/South/HYB
- 10) Recording of measurements for Labour Portio: SSE/Tele/KCG, SSE/Tele/MBNR, SSE/Tele/GWD, SSE/Tele/KRNT, SSE/Tele/MJF, SSE/Tele/MED & SSE/Tele/NZB
- 11) Bill paying authority: Sr.DFM/HYB

All Other terms and conditions, as stipulated in the tender documents shall be applicable.

T NEELA PAVANI
Sr.DSTEHYB
Digitally Signed
[View Signature Details](#)

Awarded Quantities And Rates

Item Sno.	Item Desc	Item Code	Item Qty	Qty Unit	Unit Rate(Rs)	Escl. (%)	Advt.Value (Rs)	Bid Rate/ Unit Rate	Bid Amount (Rs)
Schedule A-Schedule A (Item Directory - Not Applicable)							21840000.00		
1	(Supply portion True colour VD Items)		View Details		At Par		21840000.00	9.44 % Above	23901696.00
Schedule Totals							23901696.00		
Schedule B-Schedule B (Item Directory - Not Applicable)							1350000.00		
1	(Labour portion -True colour VD Items)		View Details		At Par		1350000.00	9.44 % Above	1477440.00
Schedule Totals							1477440.00		

Schedule C-Schedule C (Item Directory - Not Applicable)				3436021.00			
1	(Supply portion -SOR Items)	View Details	At Par	3436021.00	9.44	% Above	3760381.38
Schedule Totals				3760381.38			
Schedule D-Schedule D (Item Directory - Not Applicable)				6999713.13			
1	(Labour portion -SOR Items)	View Details	At Par	6999713.13	9.44	% Above	7660486.05
Schedule Totals				7660486.05			
Schedule E-Schedule E (Item Directory - Not Applicable)				37203863.78			
1	(Supply portion -TIB & CIB Items)	View Details	At Par	37203863.78	9.44	% Above	40715908.52
Schedule Totals				40715908.52			
Schedule F-Schedule F (Item Directory - Not Applicable)				17262223.88			
1	(Labour portion-TIB & CIB Items)	View Details	At Par	17262223.88	9.44	% Above	18891777.81
Schedule Totals				18891777.81			
Schedule G-Schedule G (Item Directory - Not Applicable)				28255800.00			
1	Comprehensive Annual Maintenance Contract.	View Details	At Par	28255800.00	9.44	% Above	30923147.52
Schedule Totals				30923147.52			
Total Value				116347621.79			127330837.28
				Rebate on Total Value (%)		0.00	
				Net Bid Value		127330837.28	

Item Breakup

Schedule	A-Schedule A					
Item - 1	(Supply portion True colour VD Items)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply of True colour OVD (Outdoor Video cum TIB Display) of 12 Line, Resolution 432 X 256, Approximate Size 14'X8' as per RDSO Specification RDSO/SPN/TC/108/ 2019, Ver.-0.0 with Amdt. 1.0 or latest. Inspected by RDSO.	Numbers	5	4368000.00	21840000.00
					Total	21840000.00
Schedule	B-Schedule B					

Item - 1		(Labour portion -True colour VD Items)				
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Installation of True colour OVD (Outdoor Video Display) , Pixel Resolution 432 X 256 with 12 Line Size 14'X8' (Feet) as per RDSO Specification RDSO/SPN/TC/108 / 2019, Ver.-0.0. Amendt.1 or latest and as per instructions of suite incharge..(All required materials for installation are to be arranged by the contractor) as per Annexure -XVIII.	Numbers	5	270000.00	1350000.00
					Total	1350000.00
Schedule	C-Schedule C					
Item - 1		(Supply portion -SOR Items)				
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply of HDPE telecom duct with outer diameter of 40mm and inner diameter of 33mm permanently lubricated as per Specn. No. RDSO/SPN/TC/45/2006 Revision 1.0 or latest or as per specification TEC GR No.G/CDS-08/02,NOV 2004 or latest . HDPE pipe shall be supplied along with 4mm dia polypropylene rope of approved quality inside wherever required. The length of HDPE telecom duct should be 1 KM. End plugs to be provided along with drum (free of cost) (2 No. per Km.).	Kilometre	30	45226.00	1356780.00
2	2	Supply of basic material to construct unit maintenance free earth consisting as per RDSO spec no.RDSO/SPN/197 ver.1.0 or latest consisting of (To be Procured from RDSO approved firm) as per bonding connections drawing no.SDO/RDSO/E&B/002. a) copper bonded steel electrode of 3.0m (min) long, 17.0 mm dia (min) with copper bonding thickness mini 250 micron and UL listed and marked--1 no. b) Earth enhancement compound of RDSO approved brand supplied in sealed bags of min 30-35 Kgs c) Copper strip of 200X25x6mm to exothermically welded to earth	Set	28	16837.00	471436.00

		electrode-1 No. d) Copper strip of 300X25x6mm (MEEB)-1 No. e) Copper strip of 150X25x6mm (SEEB)-1 nos f) Copper Tape of 25x2mm or 8mm dia-1 nos				
3	3	Supply of 35 Sq.mm Multi-strand single core PVC insulated copper cable as per IS:694 for connecting Main earth electrode to MEEB in the equipment room in duplicate.	Metre	1202	303.00	364206.00
4	4	Supply of 16 Sq mm Multi-stand single core PVC Insulated copper cable as per IS:694 for connecting MEEB to SEEB and SPDs and SPDs to MEEB.	Metre	600	144.00	86400.00
5	5	Supply of Thermo shrinkable jointing kit as per Spec. No. IRS TC. 77/2012 (Rev 3.0) Amendment.1 to 3 or latest for all types joints suitable for 6 Quad Jelly filled UG cable.(To be procured from RDSO approved firms).	Numbers	102	1923.00	196146.00
6	6	Supply of 10 Sq mm Multi strand single core PVC insulated copper cable as per IS:694 for connecting various equipments to SEEB.	Metre	1219	87.00	106053.00
7	7	Supply of terminal block 6 way PBT 25mm as per RDSO Drg.No. SA.23756/Alt.3 & IRS S.75/2006 (Rev.2) & IRS.S.23 with amendment no.2 or latest.	Numbers	3000	285.00	855000.00
					Total	3436021.00
Schedule	D-Schedule D					
Item - 1	(Labour portion -SOR Items)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Earthing and soldering of cable armour.as per instructions of site incharge (Unit Considered : Per Cable)	Numbers	808	21.00	16968.00
2	2	Supply and installation of rack mounted 12F FMS fiber part no.fms-1u 12FS 12FP Raychem/Bestnet/ Rosenberger make including 12Nos 0.2db SC /PC adaptors and 12 numbers 900 micron 1.5 meter SCPC pigtails and as specified by supervisor in-charge.(RDSO Spec	Numbers	50	9266.00	463300.00

		No.: RDSO/SPN/TC-037-2000 (Ver.3) or latest.)				
3	3	Supply and installation of rack mounted 24F FMS fiber part no.fms-1u 24FS 24FP Raychem/Bestnet make including 24Nos 0.2db SC/PC adaptors and 24numbers 900 micron 1.5 meter SCPC pigtails. RDSO Spec No.: RDSO/ SPN/TC-037-2000 (Ver.3) or latest. and as specified by supervisor in-charge .	Numbers	19	15443.00	293417.00
4	4	Laying of HDPE duct 40/33 mm dia in the trenches and in protective works already provided a per instructions of site incharge	Kilometre	38	4956.00	188328.00
5	5	Blowing of armoured optic fiber cable (OFC Cable supplied by Railways) into the duct supplied vide NS.2 of supply portion by using blowing machine and associated works. Before blowing the duct integrity shall be tested. If any defect is found during duct integrity test, the entire length of HDPE duct from one chamber to another chamber is to be replaced by the contractor at free of cost.	Kilometre	38	7382.00	280516.00
6	6	Excavation of Jointing pit and provision of joint chamber of 1.2Meter dia. Of 60 cm height with 2-piece cover on top and bottom cover with holes for drainage (reinforcement drawing will be as per technical specification).This includes water cooling of chamber, backfilling and ramming of the trench after cable laying and consolidation of soil as well as disposal of soil as per plan as advised by site engineer.	Numbers	30	3745.00	112350.00
7	7	Supply and Installation of OFC joint enclosure and splicing of Optic fiber cable (24 fibres) and testing as per technical specification No. GR OJC-2/02 Sept 2003. Supply of Splice Enclosure (24 fiber) shall be of R&M/TVS make Part No.1500-L18X-XX as per Board specification of TEC and Schedule of supply enclosed. All materials including Fusion splicing machine used for fiber splicing and, OTDR for testing and other testing	Numbers	100	6416.00	641600.00

		materials if any shall be arranged by the contractor				
8	8	Excavation of trench to a depth of 1200mm and width of 300m at bottom in all types of soil(Normal soil/soft soil/sandy soil except in hard morum / rocky soils /bridges/ level crossings/ track crossings/ coil pits,) as per RDSO Sketch no SDO/CABLE LAYING /003 including marking of cable alignment, clearing of jungle, bushes, trial pits if required, refilling with excavated soil, ramming and consolidation after laying of cables complete to the finished item of work as directed by supervisor in-charge.	Route Kilo Meter (RKM)	22	51912.00	1142064.00
9	9	Excavation of trench to a depth of 1200mm and width of 300m at bottom in hard morum soil as per RDSO Sketch no SDO/CABLE LAYING /003 including marking of cable alignment, clearing of jungle, bushes, trial pits if required, refilling with excavated soil, ramming and consolidation after laying of cables complete to the finished item of work as directed by supervisor in-charge.	Route Kilo Meter (RKM)	22	67092.00	1476024.00
10	10	Cutting of rock to a depth of 200 mm and width of 200 mm where rock is visible from surface to a depth more than 300 mm up to 550mm, excavation of trench with width 300mm above rock concreting 200mmx200mm after laying of cable with 1 cement: 2 sand : 4 graded stone aggregate 20mm nominal size and curing of concrete to the required number of days, refilling with excavated soil ramming and consolidation except in bridges, culverts, level crossings, track crossings, cable pits, rocky soil including marking of cable alignment, clearing of debris etc., complete to the finished item of work as directed by site in-charge. Drg No.SK/CN/NEW/3. All the material is to be arranged by contractor	RMT	981	241.00	236421.00
11	11	When rock is visible for more than 0.5 metre and up to 0.8 metre from ground level, excavating the trench minimum 0.5metre and maximum 0.8metre, laying 6-quad cable as	RMT	500	200.00	100000.00

		per the details shown in drawing no 3 and concreting 200mmx200mm over the rocky surface after leveling with soil/sand. (Chase cutting not required).				
12	12	Provision and laying in position cement concrete of 1 cement:3 sand:6 graded stone aggregate of 20mm normal size excluding cost of cement, centering and shuttering (including transportation of all the material) .	cum	100	2085.21	208521.00
13	13	Supply of Cement 53 grade (@ the Rate (in Rupees) of 2.2 quintals per Cu.m of concrete including transportation	Quintal	216	460.00	99360.00
14	14	Breaking of metal/ tar road and refilling after laying the cables as per drawing no.SDO/CABLE LAYING/010. The surface of the road shall be concreted to match with the old surface	RMT	750	142.00	106500.00
15	15	Transportation of materials from any Stores to Site and vice-versa including loading and unloading.- Lead above 50 Kms	MT-Km	8500	4.80	40800.00
16	16	Transportation of materials from any Stores to Site and vice-versa including loading and unloading. - Lead up to 50 Kms	MT-Km	8998	7.31	65775.38
17	17	Installation of single earth(maintenance free) including the following:- welding and fixing of copper tape (used as bus bar) welding of cable to copper plate using material supplied . All the material supplied for mounting of copper tape, exothermic weld materials, tools and fixtures for welding copper tapes shall be arranged by contractor.(As per bonding connections drawing no.SDO/RDSO/E&B/002 and as per RDSO spec no.RDSO/SPN/197 ver.1.0 or latest) a. Digging /Auguring/Boring of single earth pit of 100mm to 125 mm dia to the depth of approx. 2.8 meter. b. Insertion of 3.0 meter electrode and penetrating it at least .2 meter by pushing gently with sledge hammer where the natural soil is assumed. c. Filling of earth pit with earth enhancement	Set	20	4276.00	85520.00

		compound (EEC) in slurry from and backfilling. d. Carrying out exothermic weld connection on single earth electrode to a copper tape of 150X25X6mm. e. Carrying out exothermic weld connection on the copper tape of 150X25X6mm on earth electrode for connecting two 35 Sq mm cables for redundancy.. f. The exothermic welding material for bonding the earth system shall be procured from RDSO approved firms, which includes graphite moulds, clamps, weld metal powders. g. Digging a trench to a depth of at least 0 .5 Mtr. and run the two 35 Sq mm earth conductor (procured against supply item) from earth pit to MEEB. h. Routing and termination of two 35 sq mm earth conductors in trench from earth pit to 300X25X6mm MEEB, which is to be fixed inside the equipment room with two insulation studs. i. 525x350x250mm (inside dimension) concrete earth pit with a concrete lid, approx 50mm thick with pulling hooks, shall be provided to cover the pit. Back side of the cover will be painted in black and dare of the testing and average resistance value shall be written.				
18	18	Routing and connecting of all the SPDs in the equipment room to MEEB with 16 sq mm copper cable using copper lugs with stainless steel nut and bolts (for item procured against supply).	RMT	1205	23.00	27715.00
19	19	Routing and connecting all the equipments in the equipment/relay room to MEEB/SEEB with 10 sq mm copper cable using copper lugs with stainless steel nuts and bolts and fixtures. The work includes laying and routing the copper cable in PVC pipes/conduits and fixing them on wall.	RMT	1006	23.00	23138.00
20	20	Track crossing by horizontal boring method based on the drawing no.DRM/J/6735 dated 7-8-03 (enclosed) and as advised by the engineer at site. This includes the supply and insertion(pushing) of GI pipe	RMT	300	1403.00	420900.00

		(80mm) confirming to IS.1239 heavy class in the bore drilled with the coupler between two pipes. All the joints of casing pipes should be tight and leak proof.				
21	21	Laying different type cables in the trench. Termination covered elsewhere.	RMT	75941	5.00	379705.00
22	22	Excavation of square coil pit up to a depth of 1 Mtr. X 1.5 Mtr. For providing coil at location box, point, signals etc., This includes back filling and ramming of trench / pit after laying the cable and consolidation of soil.	Numbers	30	181.00	5430.00
23	23	Straight through / derivation with/without transformer joints: Installation Thermo shrinkable jointing kits for straight through / derivation joints for LC gate, pump houses etc where VF transformers are not required and derivatin joint by using 2T trasformer (to be housed in the joint) . This includes tapping of nominated Quad at a specific location shown by the Railway Engineer at site to the jelly field cable already laid. All material including valco tapes except thermo shrinkable jointing kit shall be supplied by the contractor. (Per Joint)	Numbers	100	979.00	97900.00
24	24	Supply and fixing of Teak Wood planks of of sizes as instructed by the site in-charge with smooth finishing surface to be provided where ever required such as in location boxes relay room, equipment room and battery room, Fine wood polish of approved quality to be applied for two times after thorough application of emery paper. Fixing bolts and wood polish supplied by the contractor painting (Teak wood, paints, fixing bolts are to be arranged by contractor).	cum	1.5	43600.00	65400.00
25	25	Supply and fixing of H. Wood planks of 40mm thick and not less than 200 mm width with smooth surface, painting (Hardwood, paints, fixing bolts are to be arranged by contractor).	cum	0.75	18673.00	14004.75

26	26	Shifting of existing cables from old location boxes / relay room to new location boxes / new cable termination racks, terminating the conductors in serial order, bunching neatly for matching the circuits with new cables as per cable plan.	Per Conductor	30110	8.00	240880.00
27	27	Carrying out circuit alterations in the existing location boxes as per the new circuits which require excavation and releasing unwanted cables from the location box and taking new cables inside the location, clamping of new cables, filling the location box with standard up to the bottom of location and plastering.	Numbers	17	612.00	10404.00
28	28	Cable termination including fixing terminals, fuses, LDs etc,. Meggering the cables and recording the readings a per the instructions of site incharge	Numbers	22396	7.00	156772.00
					Total	6999713.13
Schedule	E-Schedule E					
Item - 1	(Supply portion -TIB & CIB Items)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Supply of HD Base T Twisted Pair Transmitter, 4K UHD HDMI, Bidirectional RS232 & IR Make and Model No.Kramer TP-580 TX or better	Numbers	31	22291.00	691021.00
2	2	Supply of Twisted Pair HDBaseT Receiver, 4K UHD HDMI, Bidirectional RS232, IR Make and Model No.Kramer TP-580 RX or better or equalent from Aten/Extron	Numbers	31	22345.00	692695.00
3	3	Supply & Installation of HDMI Wireless Transmitter /Receiver set Model No. Mars 300 pro or latest with spare batteries of Make: Hollyland or better	Pair	2	38000.00	76000.00
4	4	Supply & Installation of AV Over IP Encoder, 4K Support Model Number KDS-EN-7 of Kramer make or equalent from Crestron/Black Box/Liberty.	Numbers	6	157058.00	942348.00
5	5	Supply of AV Over IP Decoder, 4K Support Model Number KDS-DEC-	Numbers	9	157058.00	1413522.00

		7 of Kramer make or equivalent from Crestron/Black Box/Liberty				
6	6	Supply of 16 port Platform Data controller as per RDSO Specn No. RDSO/SPN/TC/108/2019. Ver.0.0. Amendt.1 or latest	Numbers	20	55000.00	1100000.00
7	7	Supply of Central Data Controller with OS and operating IPIS software as per RDSO Specn No. RDSO/SPN/TC/108/2019. Ver.0.0. Amendt.1 or latestNote- This includes CCU Rack with 2 Industrial PCs, Software, CDS, UPS with minimum one hour backup, KVM Switch and all necessary connecting cables etc.	Numbers	8	725000.00	5800000.00
8	8	Supply of 2M HDMI 2.0 Cable M/M 30AWG Gold Black	Numbers	101	644.28	65072.28
9	9	Supply & Installation of 4X4 HDMI matrix switcher with scaler Model VM040HA or latest Make : crestron/Extron/AMX/Liberty	Numbers	6	85000.00	510000.00
10	10	Supply of 1x4 HDMI splitter model No. VS481B or latest Make Aten/ Kramer/Extron/Crestron	Numbers	10	16000.00	160000.00
11	11	Supply of 12 fibre mono mode armoured optical fiber cable - fibre to have nominal dia. of 8.8 µm to 9.8 µm and normal cladding diameter of 125 µm ± 1 or better. As per RDSO Spec No.IRS: TC 55 2006 (Rev.1.0) Amendment.3 or latest Make: Finolex or better	Metre	15630	41.30	645519.00
12	12	Supply of armoured outdoor LAN Cable suitable for 10BASE-T/100 BASE-TX/and 1000BASE-T (Gigabit Ethernet)-(Make: D-LINK/Comscope/ Molex/Amp/Avaya/ Krone/ Bestnet / Aamernet)	Metre	6720	88.50	594720.00
13	13	Supply of Cat 6 sheilded twisted pair (STP) Cables, Make: (Make: D-LINK/Comscope/ Molex/Amp/Avaya/Krone/Bestnet/ Aamernet)	Metre	15380	32.00	492160.00
14	14	Supply of Smart Managed Switch with 8x Gigabit Copper and 2x Gigabit dual port., hybrid mode,130 Watt PoE with two Loaded SPFs.Switch should support AV over IP & with Remote login facility. Make :TP-Link/Netgear/DLink /Cisco/Rukus or better.	Numbers	25	17700.00	442500.00

15	15	Supply of Ahuja column speaker ASC 20T Model, 15W/100V or better	Numbers	63	2915.00	183645.00
16	16	Supply of 10/100/1000(1 GBPS) single mode media converter with accessories including connecting cables. Make: MRO-TEK/D-Link/RAD/Team Engineer or better as specified by Engineer Incharge.	Numbers	73	5752.50	419932.50
17	17	Supply of 10/100 Mbps single mode media converter with accessories including connecting cables. Make: MRO-TEK/D-Link/RAD/Team Engineer or better as specified by Engineer Incharge.	Numbers	50	4000.00	200000.00
18	18	Supply of Multi Cord Binders SIZE 16 mm Make:MX or better (1.5 mts length) Make:MX or better	Numbers	130	545.00	70850.00
19	19	supply of Multi Cord Binders SIZE 22 mm Make:MX or better (1.5 mts length) Make:MX or better	Numbers	130	728.00	94640.00
20	20	Supply of 28 Port Smart Managed Switch with 24 x Gigabit Copper POE and 4 x Gigabit dual port., hybrid mode/Standard alone/NebulaFlex Cloud 375 Watt or higher PoE with two Loaded SPFs.Switch should support AV over IP & with Remote login facility. Make :TP-Link/Netgear/DLink /Cisco/Rukus or better.	Numbers	22	28200.00	620400.00
21	21	Supply of Double faced coach guidance display boards as per RDSO Specn No. RDSO/SPN/TC/108/2019. Ver.0.0. Amendt.1 or latest	Numbers	80	49000.00	3920000.00
22	22	Supply of Multi Line (5 line) Single face Train Arrival /Departure Display Boards as per RDSO Specn No. RDSO/SPN/TC/108/2019. Ver.0.0. Amendt.1 or latest	Numbers	6	825000.00	4950000.00
23	23	Supply & Installation of GPS Based, synchronization digital LED type tower clock length-12 feet, breadth 3feet and width 6 inch (approx.) LED Pitch:10 mm (Horizontal) X 10mm (Vertical). 3) LED Colour: Red (625 wavelength) or as specified by the railways, LED intensity :> 6000med, LED size: 5 mm,	Numbers	1	324000.00	324000.00

		Lighting type: Day and Night viewable, 8) Network Link: RDSO Type GPS. Other vital specifications should match RDSO/TC@ 47>47@ 2008				
24	24	supply of LC to LC Patch cords (5 mts length)with 0dB adaptors as per TEC spec G/OJC-01/03 Jan 99 or latest. Make:MX/D-Link/Bestnet Deyton	Numbers	50	1275.00	63750.00
25	25	supply of SC to LC Patch cords (5 mts length)with 0dB adaptors as per TEC spec G/OJC-01/03 Jan 99 or latest. Make:MX/D-Link/Bestnet, Deyton	Numbers	250	1275.00	318750.00
26	26	supply of SC-SC to SC-SC patch cords(3 mts length)with 0dB adaptors as per TEC spec G/OJC-01/03 Jan 99 or latest. Make:MX/D-Link/Bestnet, Deyton	Numbers	250	1275.00	318750.00
27	27	Supply of Cat-6 Patch Chord, 3m Make:MX/D-Link/Bestnet, Deyton	Numbers	40	312.70	12508.00
28	28	Supply of Cat-6 Patch Chord, 10m Make:MX/D-Link/Bestnet, Deyton	Numbers	50	578.20	28910.00
29	29	Supply of of Single Sided At A Glance Display Board in single line as per RDSO Specn No. RDSO/SPN/TC/108/2019. Ver.0.0. Amendt.1	Numbers	15	190000.00	2850000.00
30	30	Supply of one quad V.F. Transformer assembly (2T) to RDSO Spec. No. IRS: TC. 76 -2000 with Amdt.1 (or latest) with impedance ratio 470:600 Ohms.	Numbers	75	707.00	53025.00
31	31	Supply & Installation of 10 Mtr HDMI cable Make :Make: Aten/Kramer/extron/NT	Numbers	29	3540.00	102660.00
32	32	Supply and installation of 15 Mtrs HDMI Cable Make:Aten	Numbers	15	5900.00	88500.00
33	33	Supply & Installation of 1x 8 HDMI Splitter Make: Aten/Kramer/extron/NT	Numbers	13	22000.00	286000.00
34	34	Supply& Installation of 20 Meter HDMI Cable Make: Aten/Kramer/extron/NT	Numbers	9	3800.00	34200.00
35	35	Supply & Installation of Aten DP to HDMI converter 1080P	Numbers	4	2400.00	9600.00
36	36	Supply of 6F Single mode optical fiber cable Make:Finolex/ Legrand / Systimax / panduit	RMT	7200	21.00	151200.00

37	37	Supply of 20 Pair PVC switch board cable twisted in pairs PVC sheathed copper conductor 0.5mm dia (Make:Delton/Finolex/Surabhi)	Metre	500	86.00	43000.00
38	38	Supply of 6 Pair PVC switch board cable twisted in pairs PVC sheathed copper conductor 0.5mm dia (Make:Delton/Finolex/Surabhi)	Metre	2500	31.00	77500.00
39	39	Supply of 10 Pair PVC switch board cable twisted in pairs PVC sheathed copper conductor 0.5mm dia (Make:Delton/Finolex/Surabhi)	Metre	2500	48.00	120000.00
40	40	Supply, Installation , testing configuration as per site requirement and commissioning of Indoor wireless Access Points suitable to work at 2.4GHz/5Ghz open frequency band. Including all accessories licence, software up gradation & support for service etc for 3 years licence must be perpetual & to be integrated with existing Zone directors in redundant mode. Model R610 or latest of Ruckus make or better	Numbers	4	30409.00	121636.00
41	41	Supply of of Double face At A Glance Display Board in single line as per RDSO Specn No. RDSO/SPN/TC/108/2019. Ver.0.0. Amendt.1	Numbers	3	370000.00	1110000.00
42	42	Supply of Double faced Single line/Single faced Doule line train indication display boards as per RDSO Specn No. RDSO/SPN/TC/108/2019. Ver.0.0. Amendt.1 or latest (as specified by site incharge	Numbers	15	320000.00	4800000.00
43	43	Transporting and supply and installation of Concrete (RCC) route indicators at intervals of 50 meters as per technical specification. They should be of standard RCC with letters "SCR SIG/SCR 6Q/OFC cable" as per type of cable laid to drawing . In case of telecom quad cable joint locations it shall be painted with red color.	Numbers	150	807.00	121050.00
44	44	Cutting of trench across/on the platform with cutting Machine as per site requirements for laying the cable through PVC/GI pipe	RMT	4020	250.00	1005000.00

		and filling the trench after cable laying and restoring the surface with proper materials etc. and as per instructions of site in charge.				
45	45	Supply of approved quality of paint manufactured by Asian/British/Johnson and Nicholas accepted by DSTE/ASTE and Painting of all S&T gadgets in two coats duly scarping the rust as directed by SSE/SE at site, the colour to be used as per standard practice and as directed by SSE/SE at site.	Sqm	100	78.00	7800.00
46	46	Supply and placing of trucking and capping (RCC Duct) of 500mm width as per Drg. No. SDO/Cable laying /007 (Annexure-10) as Detailed in document No. RDSO/SI/G/2010 Ver1.1 or Latest on Guidelines on signalling cable laying.	Numbers	750	1278.00	958500.00
47	47	Excavation of cable trench in all kind of soil except hard rocky areas in cluding clearing of roots of tree rocks, bushes etc., to depth of 0.5 mtr-0.6 mtr to accommodate the duct under NS items and to a width of 0.5 mtr.This shall include refilling of earth as per instructions of Engineer incharge. Laying of cables is not included in this schedule in case of less depth payment will be done proportionate to depth subjected to minimum depth of 500 mm	Metre	750	150.00	112500.00
					Total	37203863.78
Schedule	F-Schedule F					
Item - 1	(Labour portion-TIB & CIB Items)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Installation of 16 port Platform Data controller in suitable capacity 9U rack with 8-16 port LIU and rack mountable power sockets.and as per instructions of suite incharge..(All required materials for installation are to be arranged by the contractor)	Numbers	20	11500.00	230000.00
2	2	Installation of Central Data Controller with CDS and configuration of all train data of station and connected devices and as per instructions of suite	Numbers	9	12000.00	108000.00

		incharge..(All required materials for installation are to be arranged by the contractor)				
3	3	Laying of 5 pair screened sheathed /CAT6/ power cable through PVC Pipe /tray as per instruction of site incharge.	RMT	129448	5.00	647240.00
4	4	Supply & fixing of 9U rack with locking front glass door and fully vented rear steel door, compatible with standard 19" accessories, top cover with gland plate and fan, with rack cage nuts and screws, fan assembly kit, rack mount shelves, Power manager.etc this includes wiring as per the instruction of site incharge. Make: HCL/ Veropresident/bestnet.or better	Numbers	15	9000.00	135000.00
5	5	Supply & fixing of 15U rack with locking front glass door and fully vented rear steel door, compatible with standard 19" accessories, top cover with gland plate and fan, with rack cage nuts and screws, fan assembly kit, rack mount shelves, Power manager.etc this includes wiring as per the instruction of site incharge. Make: HCL/ Vero president/bestnet.or better	Numbers	13	18000.00	234000.00
6	6	Supply of high quality RJ-45 shielded plug for CAT-5/6 cable Jacks.Make: D-Link/Fedus/Hiker or better.	Numbers	1420	10.75	15265.00
7	7	Supply & Installation 5MP or higher resolution Onvif POE Type IP Bullet Camera with all accessories. Make: Hikvision/Axis/Sony/Dahua Model DS-2CD2T55FWD-I5(4mm) or latest .	Numbers	80	11200.00	896000.00
8	8	Supply & Installation IP65 Enclosure boxes suitable for camera	Numbers	80	400.00	32000.00
9	9	Supply & Installation 24" Full HD LED Monitor with table top stand ,Keyboard & Mouse .Make:LG/DELL/HP/ASUS.	Numbers	7	11210.00	78470.00
10	10	Supply , instastalation and commissioning of LED type Rope light multi colour (Warm white, white, green, safron, Pink, Blue) to operate on 220V to 225V	Metre	250	149.00	37250.00

		single phase AC supply and as per the directions of site incharge				
11	11	Supply , installation and commissioning of connectors for LED type Rope light multi colour as per the directions of site incharge	Numbers	10	270.00	2700.00
12	12	Supply and fixing/laying of 25mm dia 2mm thick PVC pipe (Sudhakar/SR make) on the walls. All the required accessories such as GI clamps, Deep boxes, Jn Boxes, Normal bends, diversion bends etc are to be arranged by the contractor,as specified by supervisor in-charge.	Metre	10000	52.00	520000.00
13	13	Supply & fixing of 40 mm PVC Pipes (Make: Sudhakar/Nandi/SR) on the walls as required by the Railways. Necessary fixing the materials like screws, washers galvanized, GI clamps, wooden pegs teak etc are to be arranged by the contractor (3 clamps per metre to be used) as specified by supervisor in-charge.	RMT	500	129.00	64500.00
14	14	Supply and fixing/laying of 40mm dia 2mm thick PVC pipe (Sudhakar/Nandi/SR make) duly grooving concealed in the walls. All the required accessories such as Deep boxes, Jn Boxes, Normal bends, diversion bends etc are to be arranged by the contractor,as specified by supervisor in-charge.	RMT	1510	169.00	255190.00
15	15	Supply & fixing of 25 mm PVC casing (Modi/Donaria Make) on the walls as required by Railways at site. Necessary fixing the above like screws, washers galvanized, wooden pegs teak etc are to be arranged by the contractor (5 screws per metre to be used),as specified by supervisor in-charge.	RMT	1000	41.00	41000.00
16	16	Supply & fixing of 50 mm PVC casing & caping (Modi/Donaria Make) on the walls as required by Railways at site. Necessary fixing the above like screws, washers galvanized, wooden pegs teak etc are to be arranged by the contractor (5 screws per metre to be used),as specified by supervisor in-charge.	Metre	1000	85.00	85000.00

17	17	Supply and fixing/laying of 25mm dia 2mm thick PVC pipe (Sudhakar/Nandi/SR make) duly grooving concealed in the walls. All the required accessories such as Deep boxes, Jn Boxes, Normal bends, diversion bends etc are to be arranged by the contractor,as specified by supervisor in-charge.	RMT	5918	78.00	461604.00
18	18	Supply and fixing of PVC channels (Ganapati/Shreeram/star/similar make) with size of 1 mtr length, 150 mm x 50mm with top cover and laying the cables.Necessary fixing materials are to be arranged by the contractor. (3 anchor bolts per metre to be fixed),as specified by supervisor in-charge.	RMT	200	815.00	163000.00
19	19	Supply and fixing of PVC channels (Ganapati/Shreeram/star/similar make) with size of 1 mtr length, 50 mm x 50mm with top cover and laying the cables. Necessary fixing materials are to be arranged by the contractor. (3 anchor bolts per metre to be fixed),as specified by supervisor in-charge.	RMT	900	405.00	364500.00
20	20	Supply of GI pipes of 65mm dia Medium quality to Specn No. IS.1239 (Part-I) 1990 & galvanized to Specn IS.4736-1986 Or latest and laying /fixing over cement/girder bridges/culvert/FOB/COP/ walls, platform etc. lamping arrangement with MS brackets for fixing of GI pipes on bridges/culverts, small holes of 5mm are to be drilled on the pipe before laying of the pipes. All required materials are to be arranged by the contractor	RMT	440	345.00	151800.00
21	21	Supply & Laying of G.I Pipes 100mm dia. medium quality to specification IS.1239 (part-I) 1990 and galvanised to specification IS.4736-1986 On bridges , culverts, trench with channel ramps on either end of the culvert/bridges. Clamping arrangement with MS brackets for fixing of GI pipes on bridges/culverts, small holes of 5mm are to be drilled on the pipe before laying of the pipes.	RMT	240	351.00	84240.00

22	22	Supply and fixing of PVC Flexible pipe of different sizes 25/40/50/60mm dia as per site requirement	RMT	2500	60.00	150000.00
23	23	Installation & commissioning of Double Faced Coach Guidance Display Boards in covered area .as per RDSO Specn No. RDSO/SPN/TC/108/2019. Ver.0.0. Amendt.1 and as per instructions of site icnharge (All required materials are to be arranged by contractor).	Numbers	34	4500.00	153000.00
24	24	Installation & commissioning of Double Faced Coach Guidance Display Boardsin open area .as per RDSO Specn No. RDSO/SPN/TC/108/2019. Ver.0.0. Amendt.1 and as per instructions of site icnharge (All required materials are to be arranged by contractor)	Numbers	86	9500.00	817000.00
25	25	Installation of Multi Line (5 line) Single face Train Arrival /Departure Display Boards as per RDSO Specn No. RDSO/SPN/TC/108/2019. Ver.0.0. Amendt.1 and as per instructions of site icnharge (All required materials are to be arranged by contractor)	Numbers	6	39000.00	234000.00
26	26	Supply and installation of Calss D/C type Lightning Cum surge protection safety device with Visual indication, pluggable and testable with surge tester and potential free contacts. Outputs suitable for 48V DC applications (Conforming to RDSO Specn No. RDSO/ SPN/165/2012 or latest and should be tested as per IEC 61643) it also includes supply and installation of Surge Protection devices duly wired mounted on din rail with necessary fittings like Nuts and bolts etc. as per the site requirements and the Engineer in charge.	Set	22	5236.00	115192.00
27	27	Fabrication, supply and fixing of GI perforated Cable Tray size 200X75X2 mm including suitable cover as per the instructions of site incharge (All required materials are to bwe arranged by the contractor as per specification given in Annexure-XVIII.	Metre	2468	1020.00	2517360.00

28	28	Supply ,Installation, integration and commissioning of ONVIF 16 channel NVR 4 SATA supports up tp 6 TB of similar make Dahua/Hikvision/CP plus to model No.4416-4KS2	Numbers	6	27000.00	162000.00
29	29	Supply & fixing of 8 way RJ-45 Jack suitable for computer fixed on the modular PVC top covers including termination of cable pairs.	Numbers	320	400.00	128000.00
30	30	Supply & fixing of Dummies on PVC modular boxes 2/4/6/8 modulars.	Numbers	355	25.00	8875.00
31	31	Supply & fixing of 2 modular PVC/MS box with top plate covers on the walls. Necessary fixing materials are to be arranged by the contractor. Make: Pointer/Roma or similar	Numbers	450	110.00	49500.00
32	32	Supply & fixing of 4 modular PVC/MS box with top plate covers on the walls Necessary fixing materials are to be arranged by the contractor.	Numbers	140	127.00	17780.00
33	33	Supply & fixing of 8/6 Modular PVC/MS box with top cover on the walls.	Numbers	277	137.00	37949.00
34	34	Supply and concreting of camera poles 2' below ground level 1' above ground level including pit exacavation as per the instrcutions of Engineer incharge & specification given in the Annexure (all required materials such as SS Pole, cement sand and granite stones etc are to be arranged by the contractor) as per specification given in Annexure-XVIII	Numbers	30	38055.00	1141650.00
35	35	Supply, erection and painting of SS pole with metallic structure with floral design to cover the speakers /Cameras installed on poles 12' height, bottom pipe 4", Top pipe 3" (10' from ground level) as per specification given in Annexure.(all required materials such as SS Pole, cement sand and granite stones etc are to be arranged by the contractor).	Numbers	30	6077.00	182310.00
36	36	Supply and fixing of MS Angle fabricated camera brackets including clamps, hardware, painting, camera guards, etc.	Numbers	30	2891.00	86730.00

37	37	installation of of Single Sided,single line/Double line At A Glance Display Board in single line as per RDSO Specn No. RDSO/SPN/TC/108/2019. Ver.0.0. Amendt.1 (All reuired materials are to be arranged by the contractor	Numbers	19	18000.00	342000.00
38	38	Excavation of earth and providing earth pipe of size 50mm dia, 3.5mm thick 2.0 m. long G.I. pipe with masonry tub constructed around at earth locations as specified by site Engineer. Alternate layers of 30kgs-char coal and 30kgs-common salt to be filled in the pit while closing. The pipe perforation etc., to be carried out as per drawing No. G/SG/09/2002. The earth pipe to be connected to the function with cable as supplied by Railways. Earth reading should be less than 03 Ohms The reading should be painted on the masonry tub. The masonry tub of 300X300X300mm should be covered with cement slab. (All materials to be supplied by the contractor except cable.)	Numbers	125	5100.00	637500.00
39	39	Installation of of Single Sided, Double line,/, Double sided, single line Train Indication Display Board in single line as per RDSO Specn No. RDSO/SPN/TC/108/2019. Ver.0.0. Amendt.1 and asper instruction of site incharge (All reuired materials are to be arranged by the contractor)	Numbers	20	18000.00	360000.00
40	40	Excavation of pit, casting concrete foundation and erection of apparatus case full size as per Drg. No. SK/CN/1/89/A/1 and fixing of 1 No. of 'E' type lock for the front door, fixing of one hylam sheet of 1000mm X 940mm X 10mm thickness and painting the apparatus case inside and outside with one coat of redoxide and two coats of aluminum paints (foundation bolts and nuts,' E' type lock, cement, river sand, stone jelly of size 20/20mm, hylam sheet of size 1000mm X 940mm X 10mm, paints, varnish, fixing bolts and nuts and all other miscellaneous material required	Numbers	44	9875.00	434500.00

		for the work shall be supplied by the contractor).				
41	41	Excavation of pit, casting concrete foundation and erection of apparatus case half size as per Drg. No.SK/CN/1/89/B/1, fixing one 'E' type lock for the front door and latching arrangements for the back door and fixing of one hard wood shelf plank 37mm thick and painting the apparatus case inside and outside with one coat of redoxide and two coats of aluminum paints (foundation bolts and nuts, E type locks, cement, river sand, stone jelly of size 20/20mm, hardwood plank of 37mm thick, paints, varnish, fixing bolts and nuts and all other miscellaneous material required for the work shall be supplied by the contractor).	Numbers	30	6967.00	209010.00
42	42	Supply and installation of 50 pair cable termination box (metal box) with wago connectors complete with mounting arrangements and metallic box for indoor use with locking facility.All rrequired materials are to arranged by the contractor	Numbers	40	1833.00	73320.00
43	43	Supply and installation of 20 pair cable termination box (metal box) with wago connectors complete with mounting arrangements and metallic box for indoor use with locking facility.All rrequired materials are to arranged by the contractor	Numbers	40	1147.00	45880.00
44	44	Supply and installation of 100 pair cable termination box (metal box) with wago connectors complete with mounting arrangements and metallic box for indoor use with locking facility.All rrequired materials are to arranged by the contractor	Numbers	35	2725.00	95375.00
45	45	Supply and installation of 200 pair cable termination box (metal box) with wago connectors complete with mounting arrangements and metallic box for indoor use with locking facility.All rrequired materials are to arranged by the contractor	Numbers	35	6500.00	227500.00
46	46	Supply and installation of 400 pair cable termination box (metal box) with wago	Numbers	25	9800.00	245000.00

		connectors complete with mounting arrangements and metallic box for indoor use with locking facility. All required materials are to be arranged by the contractor				
47	47	Supply and installation of 1000 pair cable termination box (metal box) with wago connectors complete with mounting arrangements and metallic box for indoor use with locking facility. All required materials are to be arranged by the contractor	Numbers	8	129800.00	1038400.00
48	48	Supply and installation of Class-B & C Type Lightning Cum surge protection device Outputs suitable for 230V AC applications	Numbers	3	24972.50	74917.50
49	49	Supply & installation of Voltage Stabilizer, capacity: 3 KVA, 1 Ph; Input Voltage 140-270V AC; Output voltage 230V (+/-) 10%, with a double pole switch of 32 Amps.	Numbers	5	13632.00	68160.00
50	50	Fixing of horn speakers with 6mm thickness flat angles to the Electrical posts/COP available on the platform with suitable coupling arrangements as per the site incharge	Lumpsum	255	75.00	19125.00
51	51	installation and configuration of RMS as per RDSO Specn No. RDSO/SPN/TC/108/2019. Ver.0.0. Amendt.1 or latest and as per instructions of site incharge..(All required materials for installation are to be arranged by the contractor)	Set	2	12000.00	24000.00
52	52	Preparation of drawings/sketches in Auto cad format in A2 (4*A4) size to suit site requirement and submit for approval and submit the same in 2 sets in spiral binding along with soft copy	Sheet	245	600.00	147000.00
53	53	Supply & Installation of aluminum cladding /V board as per the instructions of site engineer around the TV Displays to give elegant/ aesthetic look & to Hide the Exposed cables	Square Foot	1000	295.00	295000.00
54	54	Installation of LED based, GPS based, synchronisation digital tower clock with proper protection on the roof/wall of building (All required materials	Numbers	1	50000.00	50000.00

		for fixing are to be arranged by the contracor				
55	55	Supply and installation of 8 port unmanageable switch as per instructions of Engineer in charge	Numbers	30	1300.00	39000.00
56	56	Supply of Ahuja make TZA 7000 DP Amplifier with 700 WATTS with Built-in Digital Player 2 ZONE PA MIXER AMPLIFIER	Numbers	2	47940.00	95880.00
57	57	Supply of AHUJA SRX 510 SPEAKER (400WATTS)	Numbers	2	21965.00	43930.00
58	58	Supply of Ahuja AWM-700UH/L Wireless UHF Microphones	Numbers	2	5150.00	10300.00
59	59	Supply of Ahuja AWM-700UHL Wireless UHF Microphones	Numbers	2	7380.00	14760.00
60	60	Supply of Ahuja BTA 880 Portable Speaker	Numbers	2	20620.00	41240.00
61	61	Supply of Ahuja Portable PA system WP-220M with Bluetooth	Numbers	4	7875.00	31500.00
62	62	Supply of cordless Microphone ACT-300or better.	Numbers	3	21000.46	63001.38
63	63	Supply of Ahuja SSA250M Amplifier	Numbers	14	19405.00	271670.00
64	64	Supply and Installation of CODEC with Camera Model:Cisco SX70 or above with 15 mtrs. length connecting cables.	Numbers	2	330400.00	660800.00
65	65	Supply of VMW are Server edition 2022 or latest software as per the instructions of incharge	Numbers	1	68000.00	68000.00
66	66	Supply of 10 Steps Double Telescopic Aluminum Ladder with Adjustable Hight as per the instructions of Engineer-incharge.	Numbers	17	11800.00	200600.00
67	67	Installation of GI/FRP ladder including miscellaneous items & all Necessary fixing materials are to be arranged by the contractor .GI/FRP ladder will be arranged by the Railways	Metre	1585	150.00	237750.00
68	68	Audio , Video , documentation and handing over of files in an 1 TB SSD external drive and 2 sets of hardcopies of documentation copies as per the instructions of Engineer incharge and handing over at Divisional Hqrs.	Job	2	100000.00	200000.00
69	69	Indoor and outdoor shoot (includes drone coverage) of station building and al other amenities/Locations with in the	Station	17	15000.00	255000.00

		station and handing over of station wise data in external drive & handing over at DIVISIONAL hqrs. as per the instructions of the engineer-Incharge.				
70	70	Supply and installation of Remote capture tools as per the instructions of Engineer incharge & specification given in the Annexure - XVIII	Numbers	1	175000.00	175000.00
71	71	Supply and installation of Video Editing Software (Licensed) for Content Manipilation & Publication and storage as instructions of Engineer incharge & specification given in the Annexure - XVIII	Numbers	1	59000.00	59000.00
					Total	17262223.88
Schedule	G-Schedule G					
Item - 1	Comprehensive Annual Maintenance Contract.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
1	1	Comprehensive Annual Maintenance Contract for items enclosed as Annexure-XIX for a period of 5 (Five) Years after completion of Three Years of Warranty Period.	Quarters	20	1412790.00	28255800.00
					Total	28255800.00