

1	Supply of 20 Pair PVC switch board cable twisted in pairs PVC sheathed copper conductor 0.5mm dia (Make:Delton/Finolex/ Surabhi)
2	Supply of 6 Pair PVC switch board cable twisted in pairs PVC sheathed copper conductor 0.5mm dia (Make:Delton/Finolex/ Surabhi)
3	Supply of 10 Pair PVC switch board cable twisted in pairs PVC sheathed copper conductor 0.5mm dia (Make:Delton/Finolex/ Surabhi)
4	Supply, Installation , testing configuration as per site requirement and commissioning of Indoor wireless Access Points suitable to work at 2.4GHz/5Ghz open frequency band. Including all accessories licence,
5	Supply of of Double face At A Glance Display Board in single line as per RDSO Specn No. RDSO/SPN/TC/108/2019. Ver.0.0. Amendt.1
6	Supply of Double faced Single line/Single faced Doule line train indication display boards as per RDSO Specn No. RDSO/SPN/TC/108/2019. Ver.0.0. Amendt.1 or latest (as specified by site
7	Transporting and supply and installation of Concrete (RCC) route indicators at intervals of 50 meters as per technical specification. They should be of standard RCC with letters "SCR SIG/SCR 6Q/OFC cable" as
8	Cutting of trench across/on the platform with cutting Machine as per site requirements for laying the cable through PVC/GI pipe and filling the trench after cable laying and restoring the surface with
9	Supply of approved quality of paint manufactured by Asian/British/Johnson and Nicholas accepted by DSTE/ASTE and Painting of all S&T gadgets in two coats duly scarping the rust as directed by
10	Supply and placing of trucking and capping (RCC Duct) of 500mm width as per Drg. No. SDO/ Cable laying /007 (Annexure-10) as Detailed in document No. RDSO/SI/G/2010 Ver1.1 or Latest on
11	Excavation of cable trench in all kind of soil except hard rocky areas in cluding clearing of roots of tree rocks, bushes etc., to depth of 0.5 mtr-0.6 mtr to accommodate the duct under NS items and to a width of 0.5
12	TOTAL E-Schedule
13	
14	Installation of 16 port Platform Data controller in suitable capacity 9U rack with 8-16 port LIU and rack mountable power sockets.and as per instructions of suite incharge..(All required materials for
15	Installation of Central Data Controller with CDS and configuration of all train data of station and connected devices and as per instructions of suite incharge..(All required materials for installation are to be arranged
16	Laying of 5 pair screened sheathed /CAT6/ power cable through PVC Pipe /tray as per instruction of site incharge.

17	Supply & fixing of 9U rack with locking front glass door and fully vented rear steel door, compatible with standard 19" accessories, top cover with gland plate and fan, with rack cage nuts and screws, fan
18	Supply & fixing of 15U rack with locking front glass door and fully vented rear steel door, compatible with standard 19" accessories, top cover with gland plate and fan, with rack cage nuts and screws, fan
19	Supply of high quality RJ-45 shielded plug for CAT-5/6 cable Jacks. Make: D-Link/Fedus/Hiker or better.
20	Supply & Installation 5MP or higher resolution Onvif POE Type IP Bullet Camera with all accessories. Make: Hikvision/Axis/Sony/Dahua Model DS-2CD2T55FWD-I5(4mm) or latest .
21	Supply & Installation IP65 Enclosure boxes suitable for camera
22	Supply & Installation 24" Full HD LED Monitor with table top stand ,Keyboard & Mouse .Make:LG/DELL/HP/ASUS
23	Supply , instastalation and commissioning of LED type Rope light multi colour (Warm white, white, green, safron, Pink, Blue) to operate on 220V to 225V single phase AC supply and as per the directions of site
24	Supply , installation and commissioning of connectors for LED type Rope light multi colour as per the directions of site incharge
25	Supply and fixing of MS Angle fabricated camera brackets including clamps, hardware, painting, camera guards, etc.
26	Installation of of Single Sided, single line/ Double line At A Glance Display Board in single line as per RDSO Specn No. RDSO/SPN/TC/108/2019. Ver.0.0. Amendt.1 (All reuired materials are to be arranged by the contractor