

Inventory Abstract Estimate

File No: EST-016 | Generated: 21/6/2026, 12:55:31 am

Construction of Running Room at KRNT and MLY Station. RRR KK

Division:HYB			2025-2026		
Department:S&T					
Estimate No. Y/SG/Est/25-26					
ABSTRACT ESTIMATE					
Name of the work: Hyderabad Division: Construction of Running room at MLY Station - Telecom arrangements					
S.No	Description	Qty	Unit	Rate	Total Rate
1	Supply of Stationary low maintenance secondary lead acid cells as per RDSO specification IRS: S88-2004 or latest. This includes supply of inter cell connectors, bolts, nuts, acid level indicating floats and vent plugs. 2V, 80AH	1	Numbers	3,315.0000	3,315.00
2	Calibration of Instruments at Govt approved labs as per instructions of engineer in charge. HV tester	1	Numbers	7,788.0000	7,788.00
3	Supply and Installation of HP/OEM approved	3	Numbers	72,290.0000	216,870.00

Division:HYB		2025-2026
Department:S&T		
Estimate No. Y/SG/Est/25-26		

ABSTRACT ESTIMATE

Name of the work: Hyderabad Division: Construction of Running room at MLY Station - Telecom arrangements

S.No	Description	Qty	Unit	Rate	Total Rate
	document Scanner/Printer/Fax A3/Legal size Resolution in dpi 300, speed in PPM 20, ADF capacity 50, Flat Bed Size NA, Document size Legal or latest or similar.				
4	Supply of IP Based CCTV Camera Supply of IP based day and night high resolution camera spec with IP 66 rated water proof, dust proof for outside application with RDSO SPEC. RDSO/SPN/TC/65/2013 ver. 6 or latest.	10	Numbers	27,500.0000	275,000.00
5	Installation and commissioning charges (installation	10	Numbers	3,000.0000	30,000.00

Division:HYB			2025-2026		
Department:S&T					
Estimate No. Y/SG/Est/25-26					
ABSTRACT ESTIMATE					
Name of the work: Hyderabad Division: Construction of Running room at MLY Station - Telecom arrangements					
S.No	Description	Qty	Unit	Rate	Total Rate
	and configuration for video ip camera				
6	Hiring of JCB machine (in good condition) for levelling and dressing ground/dismantling structures including disposal of debris through dumpers etc., with contractors labour, JCB machine, machine operator, fuel etc. The contractor shall arrange road permit for vehicle for all the states of operation,as per instructions of engineer in charge	1	Per Hour	1,091.0000	1,091.00
7	Segregation, stacking,	3	Per Load	10,266.0000	30,798.00

Division:HYB				2025-2026	
Department:S&T					
Estimate No. Y/SG/Est/25-26					
ABSTRACT ESTIMATE					
Name of the work: Hyderabad Division: Construction of Running room at MLY Station - Telecom arrangements					
S.No	Description	Qty	Unit	Rate	Total Rate
	loading, unloading and transportation in 6 MT capacity vehicle from Store to Scrap Depot or Store to Store within a city as per instruction of Engineer In charge.				
Grand Total Sum (₹)				564,862.00	